

Tender Inviting Authority: Registrar NID MP  
 Name of Work: Miscellaneous works at various places in the campus of NID Madhya Pradesh.  
 Contract No:

Name of the Bidder/ Bidding Firm / Company :									
PRICE SCHEDULE									
NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Including Taxes Rs. P	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words	
1	2	3	3	4	5	6	54	7	
1	<b>Railing for Faculty Cabins</b>	B1010100010100000000000000515B10100001112	350.00	Kg	575.45	201407.50	201407.50	INR Two Lakh One Thousand Four Hundred & Seven and Paise Fifty Only	
1.01	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge. (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	B1010100010100000000000000515B10100001113							
2	<b>Flooring in Workshop Block</b>	B1010100010100000000000000515B10100001114	175.00	sqm	1500.55	262596.25	262596.25	INR Two Lakh Sixty Two Thousand Five Hundred & Ninety Six and Paise Twenty Five Only	
2.01	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete. -Size of tile 600 mm x 600 mm	B1010100010100000000000000515B10100001115	20.00	sqm	1545.85	30917.00	30917.00	INR Thirty Thousand Nine Hundred & Seventeen Only	
2.02	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of tile 600 mm x 600 mm	B1010100010100000000000000515B10100001116							
3	<b>Aluminium mesh doors for Academic Block</b>	B1010100010100000000000000515B10100001117	15.00	sqm	4500.00	67500.00	67500.00	INR Sixty Seven Thousand Five Hundred Only	
3.01	Providing and fixing aluminium door with extruded built-up sections/appropriate Z sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia. and size. Aluminium sections shall be polyester powder coated sections (minimum thickness of polyester powder coating shall be 50 micron) smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle. The door shall be provided with fly-proof stainless steel grade 304 wire gage with average width of aperture 1.4mm in both directions with wire of dia. 0.50 mm all complete including fixing with necessary accessories of required size with suitable arrangement as per approval of Engineer Incharge.	B1010100010100000000000000515B10100001118							
4	<b>Car Parking Shed</b>	B1010100010100000000000000515B10100001119	35.00	cum	200.00	7000.00	7000.00	INR Seven Thousand Only	
4.01	Earthwork in excavation by mechanical means/manual means in all kinds of soil/rock in foundation including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated earth, filling the same as required and disposal of surplus excavated earth as directed, within a lead of 50 mtrs.	B1010100010100000000000000515B10100001120	1000.00	Kg	83.50	83500.00	83500.00	INR Eighty Three Thousand Five Hundred Only	
4.02	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more	B1010100010100000000000000515B10100001121	50.00	sqm	733.70	36685.00	36685.00	INR Thirty Six Thousand Six Hundred & Eighty Five Only	
4.03	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts	B1010100010100000000000000515B10100001122	10.00	cum	7997.30	79973.00	79973.00	INR Seventy Nine Thousand Nine Hundred & Seventy Three Only	
4.04	Providing and laying in position machine batched and machine mixed design mix M-25 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. (Note :- Cement content considered in this item is @ 330 kg/cum. Excess/ less cement used as per design mix is payable/recoverable separately). All works upto plinth level	B1010100010100000000000000515B10100001123	2500.00	Kg	157.50	393750.00	393750.00	INR Three Lakh Ninety Three Thousand Seven Hundred & Fifty Only	
4.05	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolting with special shaped washers etc. complete including cost of fasteners, fabrication, erection, welding and primer painting. (For payment purpose only weight of MS members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc. and nothing extra shall be paid). Hot finished seamless type tubes	B1010100010100000000000000515B10100001124	40.00	sqm	121.55	4862.00	4862.00	INR Four Thousand Eight Hundred & Sixty Two Only	
4.06	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	B1010100010100000000000000515B10100001125	300.00	sqm	575.00	172500.00	172500.00	INR One Lakh Seventy Two Thousand Five Hundred Only	
4.07	Providing and fixing of 4 mm thick FRP profiled sheet to be laid on purlins / rafters / truss structure with self-taping screws / washers of 25mm length, including material like ridges, facade, cladding, gutter, flashing etc., conveyance, labour charges, lifts, etc. all complete as per specification and direction of Engineer In-Charge.	B1010100010100000000000000515B10100001126							
5	<b>Balcony Grills</b>	B1010100010100000000000000515B10100001127	2500.00	Kg	131.00	327500.00	327500.00	INR Three Lakh Twenty Seven Thousand Five Hundred Only	
5.01	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	B1010100010100000000000000515B10100001128	60.00	sqm	121.55	7293.00	7293.00	INR Seven Thousand Two Hundred & Ninety Three Only	
5.02	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	B1010100010100000000000000515B10100001130							
6	<b>Partition for Classrooms at Academic Block</b>	B1010100010100000000000000515B10100001131							

6.01	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks. Galvanised M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each with zinc coating of 120 gms/sqm(both side inclusive)) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacturer's specification and direction of engineer in charge all complete. 66mm overall thickness Partition with 8mm thick double skin Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process with Compressive Strength 225 kg/sq.cm, Bending Strength 100 kg./sq.c	B1010100010100000000000000515B10100001132	45.000	sqm	1808.05	81362.25	81362.25	INR Eighty One Thousand Three Hundred & Sixty Two and Paise Twenty Five Only
6.02	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats	B1010100010100000000000000515B10100001133	90.000	sqm	113.90	10251.00	10251.00	INR Ten Thousand Two Hundred & Fifty One Only
<b>Total in Figures</b>						<b>1767097.00</b>	<b>1767097.00</b>	INR Seventeen Lakh Sixty Seven Thousand & Ninety Seven Only
<b>Quoted Rate in Figures</b>						<b>Select</b>	<b>0.00</b>	<b>0.00</b> INR Zero Only
<b>Quoted Rate in Words</b>						<b>INR Zero Only</b>		